

## **Pool Inspections**

The owner and agent/contractor bear joint responsibility for bringing compliance to the regulations pursuant to N.J.A.C. 5:23-2.18(c).

The owner or other responsible person in charge of work shall notify the enforcing agency when the work is ready for any required inspection specified herein or required by the Construction Official or appropriate Sub Code Official. This notice shall be given at least 24 hours prior to the time the inspection is desired. Inspections shall be performed within three business days of the time for which it was requested. The work shall not proceed in a manner which will preclude the inspection until it has been made.

### **In-ground Pools:**

**Collar Inspection** – Both Pre Collar and Collar inspections are required.

**Rough Electric & Rough Plumbing (Refer to attached diagram)** – After wire and conduit are installed, and supply and return piping an open trench and bonding inspection shall be done prior to backfill

**Final Building** - All barriers are erect, diving boards and rails are installed.

**Final Electric** - For this inspection, house access to panel box is required.

**Final Plumbing** - **All equipment installed, no interior access required**

### **Above-ground Pools:**

**Rough Electric** - After wire is installed an open trench inspection shall be done.

**Final Building** - Pool is completely installed and all barriers are in place.

**Final Electric** - For this inspection, house access to panel box is required.