

Gaslines for Pool Heaters

The following must be shown:

- * The type of material used
 - * Total developed length of
 - * Size of the gas pipe
 - * The BTU's of pool heater
 - * Plumbing Permit completed and signed by owner or contractor performing work
- * All new gas piping MUST be tested by an air pressure test
 - * Test MUST be 20lb test and MUST hold pressure at least 30 minutes before inspection
 - * Pipe and trench MUST be full exposed for inspection.
 - * All work MUST comply with the International Fuel Gas Code 2009 & IRC 2009

