



# Barnegat Township

## Construction Office

900 West Bay Avenue, Barnegat, New Jersey 08005

Tel 609.698.0080 Fax 609.698.7446

[www.barnegat.net](http://www.barnegat.net)

---

July 21, 2016

**EFFECTIVE IMMEDIATELY**

From: Martin Tellekamp  
Plumbing Subcode Official  
609-698-0080 x115

To: All Pool Contractors and Homeowners

Re: Testing and Inspection of ALL piping:

**EFFECTIVE IMMEDIATELY AS PER THE STATE OF NEW JERSEY**

With the adoption of 2015 International Codes, the 2015 International Swimming Pool and Spa Code (ISPSC) is adopted by reference as part of the Uniform Construction Code.

All underground piping for pools and spas are to be left uncovered for plumbing inspection and must be hydrostatically tested to 25 PSI and all pipes must be properly bedded in. All piping shall be run to the pump location and the test gauge installed in that area for inspection. At the same inspection, the dual main drain shall also be installed and ready for inspection as part of the test.

This procedure will help in avoiding delays and additional inspections during the pool construction process.

Many pool contractors already have this procedure in place, but moving forward it is a requirement for EVERY new pool installation. We all need to work together to protect the homeowner and complete the inspection process in the most efficient way possible.

If you have any questions, please do not hesitate to contact me at 609-698-0080 x115.

Thank you,

Martin Tellekamp